

52 4964-76

6

WC

Field

State Kansas County Kearny

Company Helmerich & Payne

Farm White - 0 #4 Well No. 84

Sec. 13 Twp. 26S Range 35W

fr N fr E fr S fr W

of NE SW NW

Contractor McNabb & Jones

Remarks Miss Test

Comm. 4-9-56 Comp. 9/5/56

Elev. 3007 DF T. D. 5227 P. B.

Pay 4966-4974 open hole = (5042-5227)
61 36°

	I. D. <u>80 BOPD</u>	R. P.
Casing Record:	13 3/8	7 <u>5042/300</u>
20	10 3/4 <u>819/550</u>	5 1/2 <u>5042/</u>
16	8 5/8	

		Tops	Sample	Log
MAR 28			Top 3402-	3414
APR 4			Next 3835-	3832
			TOR 3848-	3850
APR 11	<u>ATD 696</u>		LAN 3878-	3879
APR 18	<u>Net 10 3/4 819/550</u>		BKC 4415 -	4414
	<u>Ø 3065'</u>		Mann 4431 -	4430
APR 25	<u>DST #1 3669-80-op 1 hr</u>		Atoka 4805 -	4796
	<u>Net 360' ali 9c SW W FPO-155 Mor 4860</u>			<u>4858</u>
	<u>BH 822/20 HH 1840</u>		Miss 4980 -	<u>4980</u>
	<u>DST 3934-4024 op 1 hr</u>			
	<u>Net to 6 1/2 to 9 TS 55" - TSTM</u>			
	<u>Net 200' ali 200' MW FPO</u>			
	<u>225 BH 1010/20 HH 1845</u>			
MAY 2	<u>DST 4046-4113 op 1 hr</u>			
	<u>Net 1350 oil 49c SW FPO 50-550</u>			
	<u>BHP 1080/30</u>			
	<u>DST 4225-60 op 1 hr Net 480'</u>			
	<u>muddy SW FPO 25.500 BH 1165/30</u>			
	<u>Ø 4783</u>			
MAY 8	<u>4952-4999</u>			<u>4952-91</u>

486
382
1857

4 1/2 sd oil sho

5 1/2 sh. -

15' sd oil sho. -

7' LM sho oil

3' LM Frac sho oil

~~RTO 5227 - prep to run log & pipe~~

MAY 16 Correc

495 - or back dope

2 - 4993-5008

15' wh sdy lm nodar on stam

CD 3 5008-55

rec 37' sdy lm wh n.s show

RTO 5227 Behl 5226 set 7" 3042/300

MICT CO to ?

MAY 23 W to 5227 - bailed 4 BOPH. FRAC

8000 sd/6000 A/500 7.5 flush 240/30

subbed - 10 BOPH - 2 1/2" setpl 5000'

pg 32/4966-4974 bailed 4 BOPH.

Oil from 10,000 sd/10,000 A/500 m

flush 250 tbb oil - snuffing oil.

MAY 30 - rec all load sub 3 1/2 bbls oil

per hr T.W. PLO 4938 That 1000 Tcpl.

10,000/Kero sd/10,000 subbed load

subbed 3 1/2 bbls oil pH.

JUN 6 51

Miss 6+ 32°

JUN 13

Miss

JUN 20

~~pumping for state~~ Mor 34° +

test.

JUN 27

Miss Thru 1" Tubbing
Morrow " 2" Tubbing None

Gross over between Miss & Morrow.

Morrow pumping About 2 bbls per hr.

JUL 3 (pumping on STATE TEST)

JUL 11 no WOT.

JUL 18 pumps avg 80 bopd. FROM TO

7/25/56 - AUG 8

AUG 15 - AUG 22 - AUG 29

SEP 5

State pt 180 BOPD at 36° cov.

flow both zones commingled prod.