

FORMATION TOPS 25 26 36W NW NW SE
 Sec. Twp. Rge. Location
Kearny Kansas 3100
 County State Elevation

Magnolia Pet.
 Company

CSO Tops 1 Loucks
 Well No. Farm

Her. 2552
U.K. 2580
L.K. 2598
 Feet from _____ Line

Winf. 2630
U.F.R. 2692
 Feet from _____ Line

L.F.R. 2740
 10 3/4" 812 (400)
 6 5/8" 2799 (1000)

Producing Formation _____
 T.D. 2800 I.P. 9.240M

Date _____
Sp. 4-11-49.

R.T.D. 2800. RUST C.O. Perf. 144 holes 2733-62.
 A/1000 gals. A/6000 gals., no test. Set plug @ 2721.
 Perf. 96 holes 2696-2716. A/1000 gals. A/6000 gals.,
 no test. Set plug @ 2663. Perf. 96 holes 2638-58.
 A/1000 gals. A/6000 gals., no test. Set plug @ 2621.
 Perf. 96 holes 2598-2616. A/1000 gals. A/6000 gals.,
 no test. Set plug @ 2599. Perf. 96 holes 2576-94.
 A/1000 gals., A/6000 gals., I.P. 9.240M R.P. 382#

✓
 NOV 17 '49