

FORMATION TOPS

26 26 36W C W/2 W/2 NW
Sec. Twp. Rge. Location

Kearny Kansas 3079
County State Elevation

Magnolia Pet.
Company

CSO Tops

Her.	2512
U.K.	2538
L.K.	2560
Winf.	2594
U.F.R.	2654
L.F.R.	2700

1 Hugoton-U.S.A. "B"
Well No. Farm

1320	N Line	[Grid]
Feet from	of Sec.	
330	W Line	
Feet from		
CASING		
10 3/4"	811 ()	
6 5/8"	2767 (1000)	

Producing Formation
T.D. 2768 I.P. 15.100M

Date Sp. 4-20-49.

R.T.D. 2768. RUST C.O. Perf. 140 holes 2700-28.
 A/1000 gals. A/6000 gals., 1.230M. Set plug @ 2685.
 Perf. 120 holes 2656-80. A/1000 gals. A/6000 gals.,
 2.060M. Set plug @ 2625. Perf. 120 holes 2593-2620.
 A/1000 gals. A/6000 gals., 1.930M. Set plug @ 2583.
 Perf. 192 holes 2538-78. A/1000 gals. A/6000 gals.,
 2.500M. A/8000 gals., 2.550M. Set plug @ 2528.
 Perf. 48 holes 2513-22. A/1000 gals. A/6000 gals.,
 Drove all plugs to T.D. B.D. 4.290M. I.P. 15.100M
 R.P. 380#

2449