

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


3-26-37W

Company - WHITE EAGLE OIL CO.
Farm - Waechter No. 1

SEC. 3 T. 26 R. 37W
SE SE NW

Total Depth. 2561'
Comm. 7-19-48 Comp. 8-20-48
Shot or Treated. Acidized
Contractor.
Issued. 10-23-48

County. Kearney
KANSAS



CASING:
10 3/4" 550'
7" 2349'
5 1/2" liner 2561'

Elevation. 3046 Ind

Production. 19,500,000 Gas

Figures indicate Bottom of Formations.

sand and gravel	275
clay and gravel	300
shale blue	500
shale and sand	595
redbed and shale	624
redbed	1040
redbed and gyp	1345
anhydrite & redbed	1450
anhydrite, redbed	
and salt	1610
redbed & anhydrite	1730
redbed	1780
lime	1910
redbed & shale	2100
lime and shale	2190
lime RTD	2365
lime	2376
lime hd	2397
lime med	2404
shale red	2408
lime	2460
lime gy	2467
lime	2502
lime hd, red and	
blue shale	2510
lime	2561
total depth	

tops:

Herington	2347-2365
Krider	2371-2389
Winfield	2407-2428
Upper Ft. Riley	2454-2497
Lower Ft. Riley	2511-2556

Acidized w/13,000 gals of
HCl and 4,000 gals of 7 1/2%
acid.