

8-26-37W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY STANOLIND OIL AND GAS COMPANY

SEC. 8 T. 26 R. 37W

FARM Otto Waechter "B" NO. 1

LOC. SW SW NE

300' N. of the S. line and 150'
E. of the W. line of the NE 1/4

COUNTY Kearny

TOTAL DEPTH 2627


COMM. 12-21-50

COMP. 12-26-50

SHOT OR TREATED

CONTRACTOR

ISSUED 2-10-51



CASINO

10 3/4" 607' cem. w/400 sx
7" 2582' cem. w/300 sx

ELEVATION 3147 *3/50 Ind.*

PRODUCTION 13,367,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

surface sand	95
sand, clay	575
red bed	625
red bed, gyp	1132
gyp, anhydrite	1485
anhydrite, shale	1579
anhydrite	1750
anhydrite, shale	1885
shale	2250
shale, lime	2360
lime	2536
lime, dolomite	2605
lime	2627
Total Depth	2627

Tops:

Herington-Krider	2412
Winfield	2470
Towanda	2535
Ft. Riley	2581

Schlumberger ran to 2626

Lane Wells perforated w/6

SPF:

Herington -		
Krider	2416	2438
Winfield	2470	2490
Towanda	2535	2566

Dowell Acidized:

Ft. Riley w/2500 gal. 15%,
flushed w/4400 gal. water.

Towanda w/3000 gal. 15%,
flushed w/600 gal. water.

Winfield w/2000 gal. 15%,
flushed w/600 gal. water.

Herington-Krider w/2500
gal. 15%, flushed w/600
gal. water.

All zones w/12,000 gal. 7 1/2%,
flushed w/4000 gal water.

All zones w/12,000 gal. 7 1/2%,
flushed w/4000 gal. water.

A