


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

7-26-38W

Company - STANOLING OIL AND GAS CO.
Farm - Ora V. Martin No. 1

SEC. 7 T. 26 R. 38W
2490' S of N1 and 2490'
E of EL of NE/ NE
SW SW NE

County. Kearny
KANSAS



Elevation. 3279 ft.

Production. 16,732,000 gas

Total Depth. 2690'
Comm. 7-3-48 Comp. 7-18-48
Shot or Treated. Acidized
Contractor.
Issued. 9-25-48

CASING:

10 3/4" 598' 5 1/2" 2690'
7" 2476' cem w/900 Sx.
10 3/4" Cem w/400 Sx.

Figures Indicate Bottom of Formations.

sand, shale, gumbo	313
shale, sand	560
red bed	894
shale, sand	1150
anhydrite, shale	1283
lime, shale	1300
salt	1475
anhydrite, lime	1778
anhydrite, shale	1880
anhydrite, lime	1940
lime R.T.D.	2510
shale, lime	2520
red rock	2525
shale	2530
lime	2567
shale, lime shells	2595
lime, shale	2602
lime	2630
shale	2635
lime, shale	2640
shale	2660
lime	2690
Ran Stano Gamma Ray to	2687
Total depth	2690'

Tops:
Herington-Krider 2476'
Winfield 2530
Towanda 2595

ACIDIZATION

Chemical process W 17,000
gal 15%. No break shot.
13,000 gal flush. Max
press 125#. Broke to Vac.
Treating time 22 min.
Used 2 pump trucks.