

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Mullock,

Wichita, Kansas


10-26-39W

Company- UNTIED PROD. CO.
Farm- J. Lampe No. 1

SEC. 10 T. 26 R. 39W
NW NW SE
150' S. & E. of Center

Total Depth. 2597
Comm. 11-9-51 Comp. 11-25-51
Shot or Treated.
Contractor.
Issued. 5-17-52

County Hamilton
KANSAS



CASING:
10 3/4" 439' com. w/250' sx
7" 2501'
5 1/2" 2597'

3357 (m)
Elevation. 3347
3358 (rod)
Production. 7,000,000 Gas

Figures Indicate Bottom of Formations.

sand, clay	40
clay, sand gravel	162
shale, red rock	452
shale, gyp	630
red rock	662
red rock, gyp	830
red rock, shells	1040
red rock, lime	1240
gyp, shale, red rock	1392
red rock, shale	1650
red rock, gyp	1710
red rock, anhy. shale	1815
shale, anhydrite	1975
shale	2130
lime anhydrite	2160
shells	2190
red rock, shells	2255
shale, anhydrite	2315
lime	2352
anhy. lime	2495
1st show gas 2525'	
lime	2528
lime	2550
acidized 1000 gal. gaged 438,000 gas	
sandy shale	2566
shale	2580
inc. gas 876,000	
lime	2588
lime	2596
shale	2597
Total Depth	

Tops:
Herington 2498
Krider 2525

11-27-51 acid 3000 gal.
11-28-51 acid 2000 gal.
11-30-51 acid 2000 gal.
11-30-51 acid 5000 gal.
12- 1-51 acid 4000 gal.