

15-26-39W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Stucky Gas Unit No. 1
"B"


SEC. 15 T. 26 R. 39W
SW SW SW NE
2490' S of NL, 2490' W of EL

Total Depth. 2684
Comm. 4-21-54
Shot or Treated.
Contractor.
Issued. 10-9-54

Comp. 5-13-54

County Hamilton

KANSAS



Elevation. 3350 DF

Production. 9,978,000 Gas

CASING:

8 5/8 @ 664' w/ 400 sx cmt.
5 1/2 @ 2666' w/ 900 sx cmt.

Figures indicate Bottom of Formations.

sand & shale	295
shale	620
red bed	664
red bed & sand	1275
shale & salt	1675
shale & anhydrite	2065
shale & shells	2245
shale & anhydrite	2470
lime	2684
Total Depth	

TOPS:

Herington-Krider	2496
Winfield	2548
Towanda	2615
Ft. Riley	2666

Schlumberger ran Gamma Ray, Microlog.

Perf. 6 SPF

Towanda 2620-24, 2626-36
Winfield 2548-72, 2576-80, 2583-86,
2599-2608, 2610-13
Herington-Krider 2496-2502, 2512-16,
2520-24, 2526-29, 2531-34

Dolofrased as follows:

Treated Ft. Riley w/ 450 gal DF, 250
gal DF w/ LTC, 100 gal DF spacer, 2500
gal 10% gel acid w/ 5000# sand, 100
gal DF spacer, 1250 gal dolofrac
flush 7½%, flushed w/ 650 gal DF.

Treated Towanda w/ 450 gal DF, 250
gal DF w/ LTC, 100 gal DF spacer,
2500 gal 10% gel acid w/ 5000# sand,
100 gal DF spacer, 1250 gal dolofrac 7½%
flush, flushed w/ 65 gal DF.

Treated Winfield w/ 450 gal DF, 250
gal DF w/ LTC, 100 gal DF spacer, 3000
gal 10% gel acid w/ 6000# sand, 100
gal DF spacer, 1500 gal dolofrac
flush 7½%, flushed w/ 650 gal DF.

Treated Herington-Krider w/ 450 gal
DF, 250 gal DF w/ LTC, 100 gal DF
spacer, 2500 gal 10% gel acid w/
5000# sand, 100 gal DF spacer, 1250
gal dolofrac flush 7½%, flushed w/
650 gal water