

23 - 26 - 39W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS COMPANY
Farm- McDonald Gas Unit No. 1
"D"

SEC. 23 T. 26 R. 39W
SW SW SW NE
150' N. of SL 150' E. of WL NE $\frac{1}{4}$

Total Depth. 2682

Comm. 8-2-52


Comp. 8-20-52

Shot or Treated.

Contractor.

Issued. 11-15-52

County Hamilton
KANSAS



Elevation. 3318

Production. 18,755,000 Gas

CASING:

10 3/4" 652' cem. w/400 sx
5 1/2" 2647' cem. w/250 sx

Figures indicate Bottom of Formations.

clay & gravel	280
clay blue	472
clay blue, shale	600
red bed	685
red bed, gyp	1050
gyp, shale	1630
shale, gyp, anhy.	1650
anhy, shale	1940
shale, lime	2000
lime	2215
lime, shale	2383
lime	2605
lime, dolomite	2682
Total Depth	

Tops:

Herrington Krider	2475
Winfield	2530
Towanda	2600
Ft. Riley	2647

Ran 1 1/2" tubing set @ 2675'
Schlumberger ran Gamma Ray
& Micro Logs.

Lane Wells perforated w/6
shots per ft. as follows:

Herrington-Krider 2477-81',
2484-86', 2488-92', 2497-2501',
2509-20'.

Winfield 2530-34', 2540-46',
2548-52', 2558-62', 2575-80',
2582-88'.

Towanda 2601-06', 2610-17',
2620-22', 2630-41'.

Western Acid Co. acidized as
follows:

Ft. Riley	2500 gals. 15%
Herrington Krider	3500 gals. 15%
Winfield	3500 gals. 15%