

Company- STANOLIND OIL & GAS COMPANY
Farm- McDonald "C" No. 1
Gas Unit

SEC. 24 T. 26 R. 39W
SW SW SW NE
150' N of SL, 150' E of WL, NE $\frac{1}{4}$
24-26-39W
County Hamilton
KANSAS

Total Depth. 2720
Comm. 6-20-51 Comp. 7-8-51
Shot or Treated.
Contractor.
Issued. 9-29-51

CASING:

10 3/4" 507' cem w/450 sx
7" 2666' cem w/300 sx

Elevation 3311
3314 (2nd)
Production. 18,449,000

Figures Indicate Bottom of Formations. 20-minute Open Flow

surface sand, clay	185
clay, shale blue	370
clay, shale	580
red bed	614
red bed, shale	890
shale	1160
gyp	1175
gyp, shale	2235
shale, anhydrite	2365
shale, gyp	2446
shale, anhydrite	2552
shale, lime	2708
lime	2720
Total depth	

Tops:
Herington-Krider 2488
Winfield 2549
Towanda 2611
Ft. Riley 2666

Schlumberger run to 2720

Lane-Wells Gun Perforated
w/6 SPF as follows:

Herington-Krider 2493-2503
2506-2521
Winfield 2549-2566
2574-2580
2583-2589
Towanda 2611-2615
2617-2621
2623-2646

The Western Co. Acidized
Ft. Riley w/2500 gal 15%
flushed w/4550 gal water.
2605-2650 w/3000 gal 15%
flushed w/500 gal water.
2547-2591 w/3000 gal 15%
flushed w/500 gal water.
2486-2530 w/2500 gal 15%
flushed w/500 gal water.
All Zones w/3000 gal 7 1/2%
flushed w/3000 gal water.
All Zones w/3000 gal 7 1/2%
flushed w/3000 gal water.
All Zones w/3000 gal 6 1/2%
flushed w/3000 gal water.

