

33-26-39W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS COMPANY
Farm- Trussell Gas U."C" No. 1

SEC. 33 T. 26 R. 39W

SE SE NW

300' N. of SL & 300' W. of EL
NW/4

County Hamilton
KANSAS

Total Depth. 2554

Comm. 10-18-53

Comp. 10-29-53

Shot or Treated.

Contractor.

Issued. 12-12-53

CASING:


8 5/8" 606' cem. w/425 sx

5 1/2" 2529' cem. w/1000 sx

Elevation. 3245 DF

Production. 10,448,000 Gas

Figures indicate Bottom of Formations.



surface clay	40
clay, sand	220
clay blue, shale	550
red bed	606
red bed, gyp	1133
gyp	1200
gyp, shale, anhy.	1560
anhy.	1615
shale, anhy.	2068
shale, lime	2250
lime	2554
Total Depth	

Tops:

Herington-Krider	2350
Winfield	2407
Towanda	2470
Ft. Riley	2529

Ran 1 1/4" tubing set at 2551'
Schlumberger ran Gamma Ray
& Microlog.

Schlumberger perforated w/6 shots
per ft. as follows:

Herington-Krider 2350-82'.
Winfield 2407-24', 2428-40',
2450-58'.
Towanda 2474-2500'.

Permanent Bench Mark 5.50'
above side outlets on Braden
Head.