

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

35-26.39W

Company- STANOLIND OIL & GAS CO.
 Farm- Trussell Gas Unit No. 1

SEC. 35 T. 26 R. 39W
 SW SW NE
 150' S. of NL 150' E. of WL SE $\frac{1}{4}$

Total Depth. 2560

Comm. 4-2-52


Comp. 4-20-52

Shot or Treated.

Contractor.

Issued. 5-10-52

County Hamilton
 KANSAS



CASING:

10 3/4" 606' com. w/475 sx
 7" 2529' com. w/300 sx

Elevation. 3209

3212 (and)

Production. 12,237,000 Gas

Figures indicate Bottom of Formations.

surface sand	40
clay, sand	290
clay blue	560
red bed	875
red bed, gyp	1050
gyp	1165
shale, gyp	1440
anhy. shale	1800
anhydrite	1885
shale, anhy.	2100
anhydrite	2250
lime	2560
Total Depth	

Tops:

Herington-Krider	2352
Winfield	2398
Towanda	2472
Ft. Riley	2528

Schlumberger ran Gamma Ray
 Micro Logs

Tops:

Herington-Krider	2352
Winfield	2398
Towanda	2472
Ft. Riley	2528

McCullough Tool Co. perf.
 w/6 shots per ft. as
 follows:

Herington-Krider; 2352'-72'
 2384-87'; 2392-94'
 Winfield: 2402-10', 2414-31',
 2438-52'
 Towanda 2472-76', 2481-88',
 2492-2503', 2507-10'.

Dowell Inc. acidized as follows:

Ft. Riley	2500 gal. 15%
Herington-Krider	2500 gal. 15%
Winfield	4000 gal. 15%
Towanda	2500 gals. 15%
All Zones	24,000 gal. 7 1/2%