

508 East Murdock
Wichita, Kansas

JUN 13 1970

WELL LOG

36-26-39W
CSE NW
36-26-39W

COMPANY L.V.O. Corporation & Pan American

EARN. Marguerite Coover NO. 1

TOTAL DEPTH 6448'


COMM. 11-19-69 COMP. 12-13-69

CONTRACTOR Garvey Drilling Company

SEC. 36 T. 26S R. 39W

LOG SE NW

COUNTY Hamilton, Kansas



CASING

8 5/8" @ 1624' w/825sx (L.V.O.)

4 1/2" @ 3251' w/350sx (Pan Am.)

Spot cement plug w/60sx cement - 3600-3400 (Pan Am.)

ELEVATION 3249' KB

PRODUCTION SIGW

FIGURES INDICATE BOTTOM OF FORMATIONS

275' Surface Soils
790' Surface Sand & Red Bed
1170' Red Bed
1520' Anhydrite
2165' Red Bed & Shale
2244' Shale
2735' Lime & Shale
3995' Shale & Lime
4083' Lime & Shale
4482' Lime
4765' Lime & Shale
5206' Shale
5291' Lime & Shale
5498' Lime
5584' Lime & Chert
5657' Lime & Shale
5906' Shale & Lime
5955' Lime
6060' Shale & Lime
6071' Lime & Chert
6448' Lime & Chert
6448' RTD

Lansing 3914
Arbuckle 6380

