

Pl

STANOLIND OIL & GAS CO.  
John F. Moore No. 1.


SEC. 8 T. 26 R. 4W  
NEc SE  
2310' N SL 2310' E WL

Total Depth, 4041'  
Comm. 9-16-36 Comp. 10-13-36  
Shot or Treated, 250 Gals.  
Contractor.  
Issued, 1-16-37

County. Reno

Rotary O-4041'  
CASING:

13" 173'11"  
7" 4034'



Elevation. 1496

Production. 760 B. 2nd  
24 hrs after acid.

Figures Indicate Bottom of Formations.

red rock	30
gravel	51
shale & shells	151
shale	175
shale & shells	690
brkn lime & salt	1039
brkn lime	1418
shale & lime shells	1541
brkn lime	1873
shale	1941
brkn lime	2137
shale & shells	2292
brkn lime	2768
shale sticky	2795
brkn lime	3440
shale & shells	3458
lime	3486
brkn lime	3500
shale & shells	3596
variegated shale	3604
chat	3798
lime	3815
shale & lime shells	3836
lime	3838
shale & lime shells	3913
lime hrd	3920
brkn lime	3935
shale & lime shells	3998
shale black	4035
dolomite porous	4041
Total Depth.	

Top chat 3604  
Top Viola lime 4035

3604  
1496  
-----  
2108

4035  
1496  
-----  
2539

Natural 1st 24 hrs 14 B.  
After acid 2nd 24 hrs 760 B.