


STANOLIND OIL & GAS CO.
J.F. Moore No. 3

SEC. 8 T. 26 R. 4W
NE SE SE
990' N SL 2310' E WL

Total Depth. 4024'
Comm. 8-1-37 Comp. 9-10-37
Shot or Treated. 350 Gals.
Contractor.
Issued. 11-6-37 Rotary O-4012
Cable 4012-24

County. Reno



CASING:
13" 173'10"
6" 4012'

Elevation. 1490

Production Pot. 1574B.

Figures Indicate Bottom of Formations. 1% wtr.

red rock	110
shale & shells	149
shale lime & shells	173
shale blue & red bed	310
shale & shells	650
salt shale & lime	717
brkn lime	1022
brkn lime & salt	1155
brkn lime	1368
brkn lime & shale	1545
brkn lime	1792
shale lime & shells	1918
brkn lime	2121
brkn lime & shale	2249
brkn lime	2360
lime	2438
lime & shale brks	2523
lime	2907
brkn lime	3018
lime	3198
lime & shale break	3238
lime	3297
lime & shale break	3347
lime	3470
brkn lime	3573
variegated shale	3612
chat	3741
lime	3824
lime & shale breaks	3827
lime	3878
shale, lime & shells	3993
shale	4001
Mis ner sand	4003
shale	4018
Coring Record	
shale	4020
shale & Viola lime	4023
Viola lime	4024
Total Depth.	

4021
1490

2531

Viola lime 4021-4024

Before acid 3 hrs well swabbed
8 bbls per hr
After acid 8 hrs well flowed 1574
bbls oil 1% wtr State Pct.