

Pl.

STANOLIND OIL & GAS CO.
 Anna E. Ladd No. 1.

SEC. 9 T. 26 R. 4W
 NW SW SE
 990' N SL 330' E WL

Total Depth. 4089'
 Comm. 11-23-36 Comp. 12-22-36
 Shot or Treated,
 Contractor,
 Issued. 1-16-37

County, Reno

Rotary O-4089'
 CASING:
 13" 152'



Elevation. 1520

Production. Dry

Figures Indicate Bottom of Formations.

red rock	16
gravel & shale	105
shale & shells	665
brkn lime & salt	725
brkn lime	888
shale & lime shells	1035
brkn lime	1509
shale & lime shells	1797
brkn lime & shale	1890
shale sticky	1925
brkn lime	2306
shale & lime shells	2700
lime	2740
brkn lime & shale	2784
shale & lime shells	2857
brkn lime	2940
lime	3072
brkn lime	3327
shale & lime shells	3400
brkn lime	3511
shale & lime shells	3630
variegated shale	3643
chat	3705
chat & lime shells	3742
chat	3782
chat & lime shells	3813
lime	3845
brkn lime	3892
lime	3927
brkn lime	3936
shale	3948
shale & lime	4004
shale	4053
Misener sand	4055
shale	4066
shale & lime shells	4079
shale & pyrite	4081
shale black	4084
shale grey	4086
dolomite - slight sulphur odor, no oil show	4089
Total Depth,	

Handwritten calculations:

$$\begin{array}{r} 3643 \\ 1520 \\ \hline 2123 \end{array}$$

$$\begin{array}{r} 4086 \\ 1520 \\ \hline 2566 \end{array}$$
 V - 2566

Top chat 3643
 Top Viola lime 4086-4089