

Pl


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
Union National Bank Bldg, Wichita, Kansas.

STANCLIND OIL AND GAS CO.  
John Holtje No. "C" 1

SEC. 16 T. 26 R. 4W  
NE NE SW  
2310 N of S.L. 2310' E. of WL

Total Depth, 4058  
Comm. 6-2-34 Comp, 7-19-34  
Shot or Treated.  
Contractor.  
Issued. 8-25-34.

County. Reno.



Rotary  
CASING.

133/8" 112" 7" ●●049

Elevation. 1502

Production. Potential test  
429 B. 24 hours.

Figures Indicate Bottom of Formations.

|                            |      |
|----------------------------|------|
| shale and shells           | 735  |
| lime                       | 980  |
| broken lime                | 1110 |
| shale and shells           | 1160 |
| broken lime                | 1170 |
| lime                       | 1300 |
| shale and shells           | 1440 |
| red rock                   | 1445 |
| lime shells and shale      | 1485 |
| broken lime                | 1555 |
| lime and shale             | 1655 |
| broken lime                | 1755 |
| broken lime and shale      | 1970 |
| broken lime                | 1990 |
| lime                       | 2035 |
| broken lime                | 2200 |
| shale blue                 | 2250 |
| lime                       | 2260 |
| broken lime                | 2365 |
| brown lime                 | 2395 |
| broken lime                | 2530 |
| shale blue and lime shells | 2560 |
| lime                       | 2665 |
| broken lime                | 2750 |
| broken lime and shale      | 2825 |
| lime                       | 3245 |
| shale                      | 3255 |
| lime                       | 3315 |
| lime and shale             | 3385 |
| broken lime                | 3400 |
| lime                       | 3540 |
| shale and shells           | 3635 |
| chat                       | 3665 |
| lime                       | 3950 |
| shale                      | 4030 |
| shale                      | 4045 |

7" cemented 4052  
Drilled plug.  
4059 equals 4058 SIM.  
Top Viola 4056 SIM.  
Filled 3500' in 4 hours.  
Swab 224 bbls in 5 1/2 hours.  
Pump 162 bbls 1st 6 hours.  
Pot 429 bbls 1/4 of 1% water.  
T.D. 4058  
  
Miss lime 3035 - 3923.  
Viola lime 4056-4058

4057 (5)  
1502  
-2555

ROTARY CORING.

Cored 4045-55  
Rec 3' shale  
Cored 4055-59 no recovery.  
Top Viola 4057 (from samples)