


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

STANOLIND OIL & GAS CO.
P. Hilger "A" No. 3.

SEC. 16 T. 26 R. 4W
NE NW NW
2310' N SL; 990' E WL

Total Depth. 4040'
Comm. 8-7-36 Comp. 9-7-36
Shot or Treated.
Contractor.
Issued. 10-24-36 Rotary Tools 0-4040'
CASING:

13 3/8" 153'5"
7" 4033'7"



County. Reno

Elevation. 1492

Production. Pot. 1227 B.
Pumped.

Figures Indicate Bottom of Formations.

red rock	70
clay blue	104
red beds	112
shale, shells & salt	817
salt & lime hrd	887
shale & gyp	900
chert & sand hrd	918
brkn lime & shale	1030
shale & salt	1055
shale & lime shells	1162
lime	1203
shale & shells	1220
lime hrd	1243
shale	1250
shale & shells	1504
lime	1535
shale & shells	1795
lime	1808
shale & shells	2096
lime	2126
brkn lime	2215
sticky shale & limo	2248
lime hrd	2363
brkn lime	2379
lime hrd	2540
brkn limo	2931
limo hrd	3089
brkn lime	3279
lime hrd	3309
brkn limo	3441
shale & lime shells	3526
brkn limo	3590
variegated shale	3615
chat-Top Formation	3736
chat & shalo	3768
shalo	3778
sdv lime	3784
sand hrd	3788
lime & chat hrd	3809
sdv lime	3829
lime	3885
shale & lime shells	3901
shale	3948
shale & lime shells	4034
shale green with pyrite	4035
dolomite - free oil	4040
Total Depth.	

Coring Record

Green Shale with pyrite 4034-4035
Dolomite - free oil 4035-4040

Top Mississippi 3615
Top Viola 4035-40

Production. 1st 24 hrs. 278 B. Natural

4035
1492
-2543