

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


35-26-40W

COMPANY BRADEN DRILLING
 FARM Lake-Rhue -Sellers_N Unit 1

SEC. 35 T. 26 R. 40W
 LOC. C SE

TOTAL DEPTH 2560'
 COMM. 3-25-66 COMP. 3-29-66
 SHOT OR TREATED
 CONTRACTOR Earl F. Wakefield
 ISSUED 8-20-66

COUNTY Hamilton



CASING
 20 10
 15 8 5/8" 512' cem w/ 400 sx
 12 6
 13 5
 4 1/2" 2560' cem w/ 150 sx
 FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 3316' KB

PRODUCTION 1,500,000 CF GPD
 (Chase 2356-2530)

Surface Soil	20
Clay & Sand	110
Blue Shale	515
Shells & Red Bed	730
Red Bed & Streaks Anhydrite	1365
Red Bed & Shells	1483
Anhydrite & Shale	1656
Shale & Anhydrite	1839
Shale & Shells	1848
Anhydrite	1860
Shale & Lime	2192
Shale w/Lime	2360
Lime & Shale	2475
Lime	2560
P.T.D.	2560

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

SS

TOPS: SMP

Herrington	2343
Krider	2373
Winfield	2422
Upper Fort Riley	2490
Lower Fort Riley	2534