

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- AYLWARD DRILLING CO, ET AL
Farm- Hay No. 1

SEC. 25 T. 26 R. 8W
SE SE SE

Total Depth. 4363'
Comm. 5-29-59 Comp. 6-12-59
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 9-12-59

County Reno
KANSAS



Elevation. 1608' RB

Production. Dry

CASING:

8 5/8" 245' cem w/225 sx.

Figures Indicate Bottom of Formations.

sand & red bed	55
sand w/red bed	80
red bed	215
shale & red bed	230
shale & shells	780
salt & shale	1075
shale & lime	1350
shale	1460
lime	1532
lime & some shale	1760
lime & shale	1835
shale & lime	1890
lime & shale	2115
shale	2390
shale w/lime	2540
shale & lime	2790
lime & shale	3325
lime	3722
lime & some shale	3794
lime w/shale	3850
lime & shale	3938
chert & lime	3960
lime	3963
lime & chert	4075
lime w/some shale	4122
shale w/small amt. lime	4157
shale & lime	4218
shale	4304
shale & sand	4320
shale w/sand	4363
Total Depth	

TOPS:

Brown Lime	3270
Lansing	3286
Mississippi	3947
Kinderhook	4076
Misner	4300
Viola	4314
Simpson	4340

DST 3945-63', op 1 hr. strong blow,
rec. 865' S1. GCWM & MSW
IBHP 1440#/20", FBHP 1345#/30",
FP 50#-435#.

DST 3550-64', op 1 hr, good blow, rec.
210' gas in DP, 150' O & GCM, 120' Wtry
O & GCM, 300' O & GCMSW, 60' SW,
IBHP 1545#/20" - FBHP 1280#/30", FP 70#-
290#.

Ran Schlumberger Electric Log.