

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MESSMAN-RINEHART OIL COMPANY
Farm- Pafford Estate No. 1

SEC. 12 T. 26 R. 9W
NW NW NE

Total Depth. 4160'
Comm. 11-21-57 Comp. 12-4-57
Shot or Treated.
Contractor. Messman-Rinehart Oil Company
Issued. 3-1-53

County Reno

KANSAS



Elevation. 1674' RB

Production. 1,750,000 CFG

CASING:

8 5/8" 232' cem w/150 sx
5 1/2" 3980' cem w/75 sx

Figures indicate Bottom of Formations.

shale	45
shale & red bed	205
shale & shells - salt	1055
shale & shells	1295
Anhydrite	1330
lime & shale	1610
lime	1755
lime & shale	2030
shale & lime streaks	2130
shale	2415
lime-shells & shale	2550
shale w/lime streaks	2680
shale & lime	3367
lime	3605
lime & shale	3890
Chat "Mississippi"	3903
chert	3938
chert & lime	3951
shale-lime	3997
shale	4075
shale & lime	4160-RTD
Total Depth	

ELECTRIC LOG TOPS:

Brown Lime	3316
Lansing	3334
Mississippi Chat (Scout)	3890
Mississippian	3891
Mississippi Lime (Scout)	3942
Kinderhook	3957
Viola (Log didn't read)	4156

Perf. 3892-97' w/36^s (First 4' - 3^s per ft.
Next 1' - 4^s per ft.)