

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- MESSMAN-RINEHART OIL COMPANY  
Farm- Adkins No. 1

SEC. 15 T. 26 R. 9W  
NE SW SE

Total Depth. 4153'  
Comm. 6-28-58 Comp. 7-8-58  
Shot or Treated.  
Contractor. Messman-Rinehart Oil Company  
Issued. 9-27-58

County Reno

KANSAS



Elevation: 1689' KB

Production. 4,000,000 CFG

CASING:

8 5/8" 234' w/165 sx. cem.  
5 1/2" 4152' w/90 sx. cem.

Figures indicate Bottom of Formations.

sand and clay	140
shale and red bed	410
shale and shells	1150
shale	1190
anhydrite streak	1200
shale	1225
anhydrite	1265
shale and shells	1350
shale and lime	1830
lime	1955
lime and shale	3315
shale	3330
lime and shale	3430
lime	3720
lime and shale	3884
Mississippi Chert	3940
lime	3954
shale	3964
shale	4045
shale	4150
chert-	4153 RTD
Total Depth	

SAMPLE TOPS

Anhydrite	1225
Mississippi Chat	3892
Viola	4150

Ran Lane-Wells Log

Perforated 3891-98 ft. w/4s per ft., testing 500,000 cfg. natl.  
Treated with 300 gal. mud acid  
Frac with 5000# sand and gel acid - 330 bbls. total load