

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

OHIO OIL CO.  
W.C. Lawson No. 5

SEC 15 T. 26 R. 9W.  
SE NE NE NW  
536' fr NL 235' fr EL. NE  $\frac{1}{4}$  NW

Total Depth. 4005 P.B. 3957  
Comm. 4-23-37 Comp. 12-11-37  
Shot or Treated. 2500 gal acid.  
Contractor.  
Issued. 2-12-38

County Reno.

CASING.

12 $\frac{1}{2}$ " 101'  
10" 420'  
8 $\frac{1}{2}$ " 1861'  
7" 3642' (ripped at 3465 and cemented.  
53/16" 3878. This casing was ripped and 398'  
left in hole as a liner.



Elevation.

Production. 561,000 G.

Figures Indicate Bottom of Formations.

cellar	8	shale grey	1505	lime	2002
sand	35	lime blue hard	1530	shale soft	2 006
clay and sand	55	shale blue	1540	lime	2010
sand	95	lime blue hard	1545	broken lime	2020
red rock	135	shale blue	1560	lime	2027
red rock and sand	225	shale brown	1570	shale grey	2033
2 BW 135-45 10BW 170-225		red rock lime shells	1576	lime white	2040
rod rock	275	lime	1585	shale dark	2047
red rock and shale	346	shale grey	1595	lime	2050
shale blue	355	lime	1600	shale dark	2057
red rock	365	sdv grey shale	1612	lime	2061
red rock and shale	375	lime hard	1625	red rock	2070
red rock	405	shale and shells	1635	lime hard	2075
red rock shale & gyp	410	sdv shale	1643	water sand HFW	2088
shale and gyp	417	shale and shells	1655	lime	2117
GYP	420	sdv shale dark	1665	shale dark Cave	2120
red rock	430	sand soft	1710	lime	2123
red rock & shale	575	6 BW 1675-1690		shale rod & blk	2128
red rock	636	shale blue	1715	Cave	
shale	710	rod rock	1725	shale blue	2130
red rock	715	sdv lime hard	1733	sdv lime	2135
shale grey	740	shale dark	1750	shale	2137
lime shell	742	lime dark	1755	lime	2139
shale	825	shale light	1760	shale grey and	
salt	895	red rock	1765	shells	2146
shale blue & salt	915	lime hard	1770	sdv shale	2152
salt	935	sand sharp & hard	1790	shale and shells	2165
salt and shale	945	shale grey	1792	lime	2174
lime salt and shale	953	sand soft dry	1800	shale dark cave	2185
salt hard	1005	shale grey	1805	shale & shells cave	2190
salt and grey shale	1015	lime	1812	shale dark cave	2198
salt	1085	sand sharp & hard	1820	lime	2210
salt grey shale	1110	shale grey	1824	shale dark cave	2214
salt light	1150	rod rock	1830	lime	2216
salt hard	1190	lime	1834	shale grey	2225
salt and grey shale	1206	conglomerate red&blue	1852	rod rock	2226
lime hard	1212	Cave.		shale grey	2235
salt and grey shale	1235	lime hard	1855	lime hard	2240
lime	1247	shale	1860	sdv grey shale	2275
shale blue	1255	Cave 1834-52		shale dark	2282
salt	1280	lime	1882	lime hard	2285
shale grey & salt	1290	shale grey	1892	shale & shells	2304
lime hard	1300	rod rock	1895	lime	2308
shale light	1325	lime	1903	shale and shells	2314
lime and shale	1370	shale grey	1915	lime	2322
lime hard	1380	lime	1917	shale grey	2340
shale light	1399	shale blue	1920	lime shell	2342
lime	1412	sdv shale dark	1930	shale grey	2380
shale light	1420	lime	1932	caving 2342-50	
lime	1425	shale grey	1937	sdv shale light	2395
shale light	1430	lime	1940	lime shells	2396
lime	1440	broken lime 2BW 1945	1948	sand dry	2400
broken lime	1467	shale	1968	sand & shale	2403
shale blue	1475	lime	1980	lime shells	2405
shale grey	1490	shale blue cave	1985	shale grey cave	2420
lime	1498	red rock & shells Cave	1995	lime shell OVER	2422

15-26-9W  
 Ohio Oil Co.  
 W.C. Lawson No. 5 Reno County

sdv shale	2425	shale	3140
lime	2450	lime	3150
broken lime	2455	shale	3155
shale grey	2465	lime shells	3158
lime	2468	shale	3170
shale grey	2483	lime	3173
lime	2488	shale	3190
shale	2498	lime	3200
lime	2505	shale	3218
cave above 2498		lime	3225
shale grey	2508	shale	3350
lime	2511	3350 equals 62 SIM	
shale and shells	2515	lime	3375
lime	2523	shale blk	3378
shale and lime	2528	lime	3474
shale light	2533	show gas 3400-05	
lime	2544	sdv lime	3485
shale light	2551	lime	3505
lime	2557	2 BW 3425-85	
shale light	2565	shale	3507
lime	2578	lime	3525
shale sdv light	2582	HFW 3515-19	
lime	2590	shale	3529
lime and shale	2597	lime	3630
shale light	2604	show oil 3605-09	
lime shell	2605	shale blk	3635
shale grey & shells	2620	lime	3665
shale grey	2655	shale blk	3670
lime	2660	lime	3680
shale	2665	shale blk	3687
lime	2670	lime	3733
shale light	2674	shale	3738
lime	2680	lime	3750
shale light	2686	shale	3770
lime	2708	lime	3780
sdv lime	2722	shale	3795
2 BW 2712-15		lime	3815
sand and grey shale	2740	shale	3825
1 BW 2735-40		lime	3830
sdv shale grey	2775	shale	3835
lime	2780	lime	3840
sdv lime	2785	shale	3876
4 BW 2785		chat show gas	3878
sand	2797	lime	3885
HFW 2797		chat	3923
lime Med	2800	Gas 3900-04	
lime hard	2811	lime	3945
lime med	2825	shale	3948
lime	2900	lime	3957
LBW 2852-58		show oil 3948-51	
lime sdv blk and		shale	3985
white	2920	lime shells	3986
HFW 2920		shale	4005
lime	2954		
Gas formation	2959	Total Depth.	
Gas tried to clean hole with			
2000' of water standing in hole.			
Could not get formation sample			
2951-59 as gas carried cuttings			
up hole. Ran steel line making			
correction of 18'	2959 - 2977 SIM		
lime	2982		
sand	2985		
lime	3075		
shale	3080		
lime	3123		