


SHELL PETRO. CORP.
E. L. Adkins No. 1.

SEC. 15 T. 26 R. 9W
NE NW SE
330' fr NL 990' fr WL SE $\frac{1}{4}$

Total Depth. 4146'
Comm. 3-9-37 Comp. 4-13-37
Shot or Treated. 2000 Gals.
Contractor.
Issued. 4-24-37

County. Reno



CASING:
10 $\frac{3}{4}$ " 282'
7 " 4143'

Elevation.

Production. Pot. 2447 B.

Figures Indicate Bottom of Formations. 1,010,000 cu ft gas ED.

clay & sand	150
red rock	282
shale lime shells	515
shale & shells	900
shale & lime	1255
shale & shells	1292
lime & shale	1371
shale & gypsum	1418
lime & shale	1492
lime	1544
shale & lime	1570
lime	1607
lime & shale	1756
lime	1778
lime & shale	2410
lime	2430
brkn lime	2479
lime	2576
lime & shale	2722
shale	2770
lime	2782
lime & shale	2876
lime	2901
shale & shells	2991
shale & lime shells	3045
lime	3179
shale & lime	3355
lime	3621
lime & shale breaks	3677
lime & shale	3790
shale	3885
chat	3929
lime	3941
lime & shale	3960
shale	4113
shale & lime	4139
lime	4140
cored 4140-44	
recovery	
lime	4141
lime & shale	4142
shale brown	4143
chert	4143 $\frac{1}{2}$
chert & dolomite	4144
stain of oil	
dolomite	4146
Total Depth.	

Cored 4144-46
Stain oil 4144 $\frac{1}{2}$
Oil stained 4145
Oil stained 4146

3884