


SHELL PETRO. CORP.
Mary Whipple No. 7.

SEC. 15 T. 26 R. 9W
NE NE NE
440' fr NL 440' fr EL NE $\frac{1}{4}$

County. Reno

Total Depth. 4132'
Comm. 3-17-37 Comp. 4-16-37
Shot or Treated. 2000 & 4000 Gals.
Contractor. Olson Drlg. Co.
Issued. 5-15-37



CASING:
10 $\frac{3}{4}$ " 280'
7 " 4128'

Elevation.

Production. Pot. 3701 B.

Figures Indicate Bottom of Formations.

sand & clay	38	lime	3917
sand & red rock	275	lime & chat	3936
red rock	280	lime & shale	3945
shale	525	shale	3980
shale & shells	938	shale hrd	3990
shale & lime shells	1144	shale sticky	4014
lime	1156	shale	4039
lime & shale	1307	shale	4114
brkn lime	1378	shale & lime	4124
lime & shale	1452	Core #1	
brkn lime	1490	Cored 4124-4128 Rec. $3\frac{1}{2}$ '	
lime hrd	1560	Rec. $\frac{1}{4}$ ' limo brown	
lime & shale	1635	dense	4124 $\frac{1}{2}$
shale & shells	1668	Rec. $\frac{3}{4}$ ' shale green	4125
lime	1733	Rec. $2\frac{1}{4}$ ' shale brown	4127 $\frac{1}{2}$
lime hrd	1778	Rec. $\frac{1}{4}$ ' chert & dolomite	
red bed	1795	oil stained	4128
shale & lime shells	1983	dolomite, oil stained	4129
shale & shells	2106		
lime & shale	2182	Core #2	
shale & shells	2474	Cored 4128-4132, Rec. 2'	
lime & shale	2505	Rec. 1' cement	4129
shale	2540	Rec. 1' dolomite -	4130
brkn lime	2591	No rec. chert	4130 $\frac{1}{2}$
shale	2638	No rec. chert &	
lime hrd	2646	dolomite	4132
brkn lime	2661	Total Depth.	
lime & shale	2731		
brkn lime	2802		
shale	2854	Well gaugec 1,560,000 gas	
lime	2903		
shale	2970		
brkn lime	3010		
lime	3022		
brkn lime	3090		
lime	3117		
brkn lime	3131		
lime	3231		
lime & shale	3335		
lime hrd	3376		
lime med hrd	3386		
lime hrd	3395		
lime hrd	3443		
lime sft	3463		
lime hrd	3472		
lime med sft	3479		
lime hrd	3501		
lime med hrd	3506		
lime hrd	3545		
lime med sft	3550		
lime sft	3557		
lime med sft	3560		
lime hrd	3622		
lime	3680		
lime & shale	3775		
shale	3860		
chat	3895		
lime & chat	3897		