


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MESSMAN-RINEHART OIL CO.
Farm- Montford "C" Unit No. 1

SEC. 16 T. 26 R. 9W
NE SE SE

Total Depth. 4159'
Comm. 4-16-58 Comp. 5-12-58
Shot or Treated.
Contractor, Messman-Rinehart Oil
Issued. 7-5-58

County Reno KANSAS



Elevation. 1693' KB

CASING:
8 5/8" 233' cem w/165 sx.
5 1/2" 4156' cem w/175 sx.

Production. 110 BOPD & 14% Wtr.
4,000,000 CFG

Figures Indicate Bottom of Formations.

clay & sand	150
shale & shells	525
shale	1200
anhydrite streak	1215
shale	1242
anhydrite	1275
shale & shells	1495
lime & shale	1620
lime	1955
lime & shale	3265
lime & shale	3375
lime	3740
lime & shale	3886
chat Mississippi	3920
chert	3943
lime	3959
lime & shale	3990
shale	4154
lime	4157 RTD
lime	4159
Total Depth	

TOPS:
Anhydrite 1242
Brown Lime 3340
Lansing 3372
Mississippi Chat 3886
Mississippi Lime 3943
Viola 4154

5-5-58 - Treated 4156-4159' w/250 gal.
acid, testing.
5-9-58 - Perf. 3890-3896' w/24 shots,
Acidized w/400 gal. mud acid.
5-10-58 - Frac - 5000 gal. geo-frac
and 5000# sand.