


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. MESSMAN-RINEHART OIL CO.
Farm. Woodson No. 1

SEC. 20 T. 26 R. 9W
C E/2 E/2 SE/4

Total Depth. 4230'
Comm. 3-28-58 Comp. 4-11-58
Shot or Treated.
Contractor. Messman-Rinehart Oil
Issued. 7-5-58

County Reno KANSAS



Elevation. 1721' KB

Production. 3,500,000 CFG

CASING:

8 5/8" 230' cem w/150 sx.
5 1/2" 4230' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay & sand	180
shale & shells	230
red bed, shale,	
shells	830
shale, shells, salt	1260
Anhydrite	1300
shale & shells	1330
shale & lime	1535
lime	1700
lime	1870
lime & shale	2640
shale	2900
lime & shale	3068
lime	3215
lime & shale	3430
lime	3805
lime & shale	3870
lime - shale - chert	
(Miss.)	3942
chert	3983
lime & shale	4005
shale	4150
lime & shale	4215
lime & chert	4230 RTD
Total Depth	

TOPS: LOG	
Brown Lime	3384
Lansing	3420
Mississippian	3927
Kinderhook	3999
Viola	4199

4-18-58 - Perf. 3925-30 w/4 shots per ft.
Treated w/300 gal. mud acid -
tested 1,200 Mcf.
4-19-58 - Frac, w/2500# sand & 3000 gal.
gal.