


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HARMS & BURT DRILLING
 Farm- Jones No. 1

SEC. 26 T. 26 R. 9W
 NE NE SE

Total Depth. 4433'
 Comm. 11-8-54 Comp. 11-26-54
 Shot or Treated.
 Contractor.
 Issued. 4-2-55

County Reno KANSAS



CASING:
 8 5/8" 210' cem w/300 sx

Elevation. 1670' RE

Production. Dry

Figures indicate Bottom of Formations.

clay	40
sand	85
red bed	210
red bed, shale	580
shale & shells	1157
anhydrite	1178
shale, salt	1305
anhydrite	1360
anhydrite, shale	1425
shale, shells	1490
lime & shale	1695
lime	1960
lime, shale	2645
lime	3160
lime, shale	3245
shale, sand	3270
shale, lime	3345
brn lime & shale	3359
lime	3640
lime, shale	3675
lime	3740
lime, shale	3942
lime, chert	3987
lime, shale	4110
shale, shells	4130
lime, shale	4191
shale, lime	4211
chert w/lime	4221
lime, chert	4228
chert	4245
chert, lime	4288
shale, sand	4305
sand	4307
shale, sand	4376
sand	4383
lime	4407
lime	4433
Total Depth	

#3 open 1 hr., shut in 30 mins., 3230'
 salt wtr., IFP 120#, FFP 1533#,
 BHP 1653#.

Tops: Scout	
Heebner	3179
Toronto	3210
Douglas Sand	3255
Iotan	3345
Lansing	3360
Mississippi	3744
Kinderhook	4007
Viola	4211
Simpson Shale	4288
Simpson Sand	4294
Arbuckle	4384

Drill Stem Tests:

#1 4209-21, open 1 hr., shut in 30 mins., 115'
 salt water, IFP 14#, FFP 54#, BHP 1240#.

#2 4287-4305, open 1 hr., shut in 30 mins.,
 10' mud BHP 0#