

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - THE DRILLERS GAS CO.
Farm - Southwestern College No. 3

SEC. 2 T. 27 R. 1W
C S/2 NE SW

Total Depth. 3402 $\frac{1}{2}$
Comm. 10-2-49 Comp. 11-16-49
Shot or Treated.
Contractor. Springer & Harper
Issued. 12-24-49

County. Sedgwick
KANSAS



CASING:

8" set @ 202' w/150 sx.
5" set @ 3394' w/125 sx.

Elevation. _____

Production. Est. 30 Bbls.

Figures Indicate Bottom of Formations.

Sand	55
Shale	185
Lime	230
Anhydrite, shale	330
Anhydrite	345
Shale	350
Red rock	360
Lime - shale	970
Sandy lime	985
Shale - shells	1180
Sand	1325
Shale - shells	1400
Lime	1445
Shale - lime	1692
Lime	1750
Lime - shale	1925
Lime	2170
Lime-shale	2395
Shale	2592
Lime	2725
Shale - lime	2805
Shale	2840
Shale - lime	3076
Miss. lime	3115
Lime	3190
Lime - chert	3220
Lime	3292
Shale	3385
Viola	3390
Simpson	3402 $\frac{1}{2}$

Total Depth

FORMATION TOPS:

Kansas City	2592
Mississippi	3076
Viola	3385
Simpson	3390