


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE DRILLERS PROD. CO.
 Farm- Ott No. 5

SEC. 2 T. 27 R. 1W
 SW NW SE

Total Depth. 2707
 Comm. 10-10-51 Comp. 1-2-52
 Shot or Treated.
 Contractor. Springer & Harper
 Issued. 2-16-52

County Sedgwick
 KANSAS



CASING:
 10" 205' cem. w/250 sx
 7" 2699' cem. w/100 sx

Elevation. 1327 RB

Production. Pmp. 25 bbls.

Figures indicate Bottom of Formations.

sand	55
shale & shells	180
anhydrite	240
lime & shale	485
lime	535
lime & shale	595
lime	630
lime & shale	690
lime	720
lime & shale	1130
shale	1315
sand lime & shale	1395
shale	1445
shale & shells	1560
lime	1620
shale	1655
lime	1825
lime & shale	1870
lime	2115
lime & shale	2130
shale	2270
shale & lime	2305
lime	2365
shale	2423
lime	2450
lime & shale	2480
shale	2587
lime	2707
Total Depth	

Tops:
 Kansas City 2584

DD 2705½
 500 acid
 3000 acid
 PB 2700
 Sqz 250 sks cement
 DD 2707
 15 # 2699½ - 2704½
 500 Acid
 ½ BO & 5½ BWPH
 1000 Acid