

WELL LOG BUREAU— KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - DRILLERS PRODUCTION CO.
Farm - P. Widner No. 1

SEC. 2 T. 27 R. 1W
SE NW NE

Total Depth. 2727
Comm. 3-22-51 Comp. 5-10-51
Shot or Treated.
Contractor. Springer & Harper
Issued. 6-23-51

County. Sedgwick
KANSAS



CASING:
10" 210' cem w/250 sx
7" 2727' cem w/125 sx

Elevation. 1328 R.R.

Production. dry

Figures Indicate Bottom of Formations.

sand	90
shale	110
shale, shells	165
anhydrite	250
lime, shale	365
lime	400
shale, lime	480
lime	575
lime sandy	600
shale, lime	1790
lime	1930
shale, lime	2320
lime	2387
shale, lime	2495
shale	2585
lime	2727
Total Depth	

Tops:
Brown Lime 2265
Lansing 2305
Kansas city 2585

DST: 2588-03, open 30 min.
Rec. 30' mud.

CO to 2723
18 Shots 2704-08, show oil
and water.

Acid 750 Squeeze
41 Shots 2696-2710
Acid 500 Squeeze
24 Shots 2699 $\frac{1}{2}$ -2704
Acid 2000
Pump 4 BFPH - 99% wtr.