

Location SE SW SW


Sec. 2 T. 27 R. 1W

330' SL 1115' WL SW 1/4

Casing Record

County- Sedgwick

10" Farm- Curry No. 1
 20" 8 1/2" Company- Plains Oil Co.
 15 1/2" 6-5/8" Con.-
 12 1/2" 5-3/16" Comm.- 7-2-29 Comp.- 10-27-29
 Total Depth 3401' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 250 bbls per day

Date Issued. 11-2-29

(DEEPENING RECORD)

| Formation | Depth | Formation | Depth | Formation | Depth |
|------------------|-------|-------------------|-------|---------------------|----------|
| quick sand | 40 | lime sdy | 1320 | lime | 2771 |
| sand | 50 | shale lgt | 1325 | shale | 2842 |
| shale blue | 53 | shale blk | 1359 | lime | 2845 |
| shale blue | 100 | lime | 1377 | shale | 2855 |
| shale 10 BW180- | 185 | shale | 1385 | red mud | 2858 |
| 185' | | lime | 1395 | shale | 2875 |
| shale sdy | 200 | shale blue | 1405 | lime | 2915 |
| HFV 185-90' | | lime | 1420 | lime sdy | 2970 |
| shale | 218 | shale | 1425 | shale | 2995 |
| lime | 223 | lime | 1440 | lime | 2997 |
| lime | 250 | shale | 1450 | shale | 3035 |
| slate blue | 255 | lime | 1470 | lime brkn | 3043 |
| shale blue | 260 | shale blue | 1490 | red rock | 3050 |
| lime | 280 | lime sdy | 1525 | mixed shale & red | |
| shale | 300 | shale blue | 1545 | rock | 3077 |
| lime | 330 | lime | 1550 | chat S.O. 3094 | 3114 |
| shale blue | 355 | lime | 1585 | shale | 3116 |
| lime | 385 | shale | 1590 | chat | 3143 |
| shale | 395 | lime | 1625 | lime sdy | 3160 |
| lime | 400 | shale blue | 1635 | lime | 3243 |
| shale | 410 | lime | 1650 | red rock | 3245 |
| red rock | 415 | shale sdy | 1655 | lime | 3285 |
| shale | 420 | 1 1/2 BW 1650-55 | | shale | 3296 |
| lime | 445 | shale blk | 1670 | lime | 3298 |
| shale | 455 | lime | 1720 | shale | 3330 |
| red rock | 465 | shale | 1735 | shale | 3349 |
| shale | 475 | lime | 1790 | lime sdy | 3350 |
| lime | 485 | shale | 1795 | | |
| shale | 490 | lime | 1840 | shale | 3388 |
| lime S.G. 500-10 | 520 | shale sdy | 1850 | Simpson Dolomite | 3390 |
| shale | 525 | lime | 1995 | Cherty Dol. with | |
| lime | 535 | 10 BW 1975-80 | | less than 5% sand | 3390 1/2 |
| shale | 545 | sand | 2010 | Dol. & sand | 3392 |
| lime | 575 | HFV 1995-2005' | | sand & 10% cherty | |
| lime sdy | 630 | lime | 2036 | dolomite | 3393 |
| slate blue | 635 | shale | 2037 | sand & small amount | |
| shale | 640 | lime | 2045 | dol. & chert | 3394 |
| lime 1BW 640-55 | 655 | shale | 2053 | quartz sand | 3401 |
| shale | 660 | lime | 2065 | | |
| lime | 700 | shale | 2080 | Total Depth | 3401 |
| shale blue | 710 | lime | 2097 | | |
| lime | 725 | shale | 2102 | | |
| shale blue | 735 | lime sdy | 2145 | | |
| red rock | 745 | shale | 2180 | | |
| shale blue | 755 | lime sdy | 2190 | | |
| lime | 760 | shale | 2265 | | |
| shale | 765 | lime 1BW 2180-90 | 2285 | | |
| lime | 780 | shale | 2317 | | |
| shale blue | 800 | sand 3BW 2317-25 | 2325 | | |
| lime | 820 | lime | 2355 | | |
| shale blue | 825 | shale | 2442 | | |
| lime | 885 | lime | 2450 | | |
| red rock | 890 | shale | 2555 | | |
| shale blue | 920 | shale | 2595 | | |
| shale blk | 930 | lime sdy | 2610 | | |
| lime | 1040 | Show Oil 2600-05' | | | |
| 4 BW 950-960 | | lime 2660 water | 2678 | | |
| shale | 1045 | lime sdy | 2688 | | |
| lime | 1055 | lime | 2705 | | |
| shale | 1145 | shale | 2708 | | |
| shale lgt | 1225 | lime sdy | 2715 | | |
| shale sdy | 1280 | 2710-13 Oil | | | |
| shale | 1300 | lime | 2735 | | |
| 10 BW 1240-80 | | shale | 2737 | | |