

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - DRILLERS GAS CO.
Farm - Slease No. 2

SEC. 11 T. 27 R. 1W
CW $\frac{1}{2}$ NE NW

Total Depth. 3430 R. B.
Comm. 11-16-49 Comp. 12-28-49
Shot or Treated.
Contractor. Springer & Harper
Issued. 2-4-50

County. Sedgewick
KANSAS



Elevation. _____

Production. Est 20 bbls.

CASING:

8 5/8" 216 cem. w/250 sx. surfaced
5 1/2" O.D. 3421' cem. w/250 sx.

Figures Indicate Bottom of Formations.

surface clay & sand	55
shale & shells	216
anhyd.	370
anhyd. & shale	445
shale & shells	610
shale & lime	705
sand	718
lime	850
lime & shale	1025
shale & shells	1290
sand	1325
lime & shale	1580
shale & shells	1775
lime	1810
shale	1850
lime	1920
limestone sdy	1935
lime	2060
shale blk	2080
lime & shale	2125
shale	2310
lime & shale	2550
shale	2590
lime	2820
shale & shells	2990
shale & lime	3130
lime	3285
lime & shale	3330
shale	3410
shale & shells	3422
Simpson sand	3425
Sand	3430
Total depth RB	
Tops:	
Kansas City	2589
Miss.	3080
Kindershook-	3329
Simpson	3419

2500' WIH @ 3430
12 S 3080-84 wtr
24 S 2708-15

200 gal acid