

30-27-10W


SKELLY OIL COMPANY.
F. E. Miles No. 5

SEC. 30 T. 27 R. 10W
NWc NE

DEEPENING RECORD

Total Depth. 4220'
Comm. 5-9-34 Comp. 6-28-34
Shot or Treated.
Contractor. Southern and Thurmond.
Issued. 11-29-41

County. Kingman.



CASING.

12 $\frac{1}{2}$ " 317' 7" 3390'

Elevation.

Production. Potential flow
250 B. 24 hours.

Figures Indicate Bottom of Formations.

surface sand	70	lime	3060
sand shells	135	shale	3085
sand shells lime bed	210	lime	3125
sand rock	280	lime and shale	3150
sand rock shells	330	shale	3170
sand rock shale and shells	545	lime	3175
shale shells	932	lime	3220
salt and shells	1174	lime and shale	3240
salt	1274	shale	3255
shale and shells	1555	lime broken	3285
lime	1600	lime and shale	3335
shale and shells	1735	chert and lime	3350
shale and broken lime	1810	lime	3380
lime and shale	2060	3380 equals 3382	
shale and shells	2185	Cable.	
lime and shale	2365	coring	3398
lime	2410	lime	3428
lime and shale	2475	lime 1st oil	3435
shale and shells	2540	lime	3440
lime	2580	Run measuring line	3462
lime shells and shale	2635	lime	3472 $\frac{1}{2}$ TD
lime	2675		
shale and shells	2725		
lime shale	2805		
shale and shells	2875		
shale	2945		
shale and lime	2975		
shale and shells	3000		
lime	3075		
shale	3094 SIM		
plugged back with cement top 2775			
cement	2850		
cement shale	2888		
shale	2990		
Plugged back 2990 to 2385			
SIM 2560			
cement	2645		
cement shale	2660		
cement	2725		
cement shale	2780		
cement	2801 SIM		
shale and lime	2815		
shale and cement	2827		
cement	2840		
shale and cement	2910		
shale and shells	2940		
lime	2975		
shale	2980		
lime	3000		
lime shells and shale	3015		
lime and shale	3040		

DEEPENING RECORD

Comm. 7-15-41 Comp. 7-30-41
Prod. 34,129,000 Gas
Tops: Kinderhook 3892
Viola 3960
Simpson 4052
Arbuckle 4155
Total Depth 4220

4 $\frac{1}{2}$ " csg cemented at 4201
Perf. w/100 holes 4156-72
Gas gauged 13,860,000 cu ft
Treated w/1500 Gals. Acid
Gas gauged 34,129,000 cu ft