

30-27-10W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.

Farm- F.C. Miles "A" No. 3

SEC. 30 T. 27 R. 10W  
CWL NE $\frac{1}{4}$ 

Total Depth. 3579'

Comm. 8-16-33


Shot or Treated.

Contractor.

Issued. 7-12-58

DEEPENING RECORD:

Comp. 9-26-33

County Kingman  
KANSAS

Elevation. \_\_\_\_\_

Production. 1102 bbls.

CASING:12 $\frac{1}{2}$ " 228'

6 5/8" 3396'

Figures indicate Bottom of Formations.

|                      |                    |                                |      |
|----------------------|--------------------|--------------------------------|------|
| sand                 | 60                 | and odor                       | 3525 |
| red rock, shale      | 245                | gy to brwn limestone           | 3540 |
| red rock             | 300                | Buff to brwn limestone         | 3542 |
| shale, lime shells   | 515                | shale                          | 3551 |
| shale, shells        | 1375               | gry dolomitic lime             | 3565 |
| lime, shells         | 1545               | shale                          | 3571 |
| shale, lime shells   | 1840               | lime                           | 3575 |
| lime shells          | 1910               | dolomitic lime                 | 3579 |
| shale, lime          | 2095               | Total Depth                    |      |
| lime, shells         | 2145               |                                |      |
| lime, shale          | 2235               | ACID TREATMENT #2 - between    |      |
| lime, shells         | 2305               | 3396-3514' w/500 gals. 1-29-58 |      |
| shale                | 2360               |                                |      |
| lime                 | 2390               | ACID TREATMENT #3 - between    |      |
| shale, lime          | 2550               | 3396-3551' w/500 gals. 2-1-58  |      |
| lime                 | 2560               |                                |      |
| shale                | 2590               | ACID TREATMENT #4 - between    |      |
| shale, shells        | 2615               | 3396-3579' w/500 gals. 2-4-58  |      |
| shale                | 2630               |                                |      |
| lime, shale          | 2855               |                                |      |
| lime                 | 2890               |                                |      |
| shale, shells        | 2925               |                                |      |
| lime                 | 3005               |                                |      |
| shale                | 3055               |                                |      |
| 3055 = 3071 SLC      |                    |                                |      |
| shale, lime          | 3260               |                                |      |
| shale, shells        | 3295               |                                |      |
| lime, shells         | 3303               |                                |      |
| shale, shells        | 3317               |                                |      |
| lime, shale          | 3377               |                                |      |
| casing 3377-94       |                    |                                |      |
| lime, shale          | SIM 3397           |                                |      |
| Cable tools          |                    |                                |      |
| oil, gas small show  | 3406               |                                |      |
| lime                 | 3420               |                                |      |
| lime gr brwn         | 3439               |                                |      |
| oil, gas             | 3427-36.           |                                |      |
| Est. gas             | 130 M. Flowed      |                                |      |
| 5 BPH                | 2000' oil in hole. |                                |      |
| sdv lime brwn, shale | 3446               |                                |      |
| Gas Increase         |                    |                                |      |

lime 3456  
Total Depth

DEEPENING RECORD:

Comm-10-28-57 Comp-3-9-58

I.P.-3 $\frac{1}{2}$  BO & 115 BHPD

T.D.-3579'

shale w/scattered strks

lime 3467

shale 3472

brwn lime 3480

shale 3490

dolomitic lime 3499

shale 3505

brwn lime 3510

Good saturation &amp; stain

limestone, no shows 3514

brwn limestone w/dead

oil stain 3520

Buff limestone w/stain