

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bldg, Wichita, Kansas.

SKELLY OIL COMPANY.
 So. Miles No. 2

SEC. ³⁰~~29~~ T. 27 R. 10W.
 NWc SE
 330' fr NL 330' fr WL.

Total Depth. 3466
 Comm. 11-15-35 Comp. 12-13-35,
 Shot or Treated, 4000 gal
 Contractor. Southern and Thurmond.
 Issued, 2-15-36

FEB 15 1936
 County. Kingman.

Rotary 0 to 3412
 Cable 3412-3466

CASING.

12 $\frac{1}{2}$ " 303 . 7" 3410'



Elevation.

Production. 136 B.O after Pot
 shot and Est 80,000 gas.

Figures Indicate Bottom of Formations,

surface soil and sand	75	
ree bed and sand	125	no saturation or porosity 1 hour test.
red bed shells and sand	260	showed 25 gal salt water with scum oil.
red bed and shells	329	lime hard grey and brown 3455
red bed shells and shale	655	lime grey 3458
shale and shells	940	lime grey with little brown lime 3460
salt	960	lime grey 3466
salt gyp and shells	1320	Total Depth.
shale and lime shells	1420	
lime	2755	Some porosity and oil s tatin 3460
shale and lime	2805	no saturation or porosity 3463
lime	2880	no saturation or porosity 3466
shale and lime	2910	
lime and sdy lime shells	2970	
lime	3005	Lansing 3407-66
broken lime	3050	
lime	3085	
broken lime	3130	
broken lime & shale	3210	
broken lime	3225	
lime	3325	
broken lime and shale	3370	
shale	3402	
cored 3402-3412 Rec. 5'.		
Top 3' Dense grey lime fossiliferous		
Bottom 2' dark grey and brown cherty		
lime little porosity and no saturation.		
fine brown and grey lime	3415	
coarse grey lime	3432	
brown and grey lime	3436	
dense grey light lime with 25% dolomitic		
lime	3440	
brown and grey lime	3448	
first 2' hard next 3' med soft some		
Saturation and pososity. little free		
oil in hole.		
lime hard light	3451	