

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. CSL NE $\frac{1}{4}$

Sec. 30 T. 27 R. 10W

DEEPENING RECORD

Casing Record.

County.

Kingman

10"

Farm. Miles

" "

No. 2

20"

8"

Company. Skelly Oil Co. ✓

15"

65/83373

Contr.

12"

220 53/16"


Comm. 4-15-33

Comp. 5-26-33

Total Depth. 3640

Shot

Quarts Between.



Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 4-10-48

240 Bbls

Formation	Depth	Formation	Depth.
sand	18	lime grey and brown little shale	3384
sand	220	shale dark 10% brown lime	3390
shale	239	lime brown shale	3406
sdv shale	700	lime brown & grey and little	
sand shale and lime shells	970	shale	3427
sdv shale, shells sand & shale		lime brown and grey oolitic	3431
and shells	1380	Oil	3425
broken lime and shale	1510	lime brown grey	3436
shale shells	1600	lime brown and little chert and	
lime shells	1690	sand	3453
lime and sdv shale	1770	lime brown	3469
broken lime, sandy shale	1850	lime brown little chert	3478 $\frac{1}{2}$
lime, sand and shale	1935	TD.	
lime and sand	1985		
lime and sdv shale	2075	20" 18' conductor	
lime and shale	2140		
lime and shale	2195		
sand and shale and lime shells	2265	<u>DEEPENING RECORD</u>	
lime shale	2300	Comm. 9-1-45 Comp. 10-25-45	
shale	2320	Production - Dry	
sand and lime	2355		
sdv shale and lime shells	2410	lime gy	3478 $\frac{1}{2}$ - 3518
sdv shale and lime	2470	lime brwn & gy	3526
sdv shale	2525	lime gy hd	3542
sdv shale lime shells	2565	lime gy & shale	3553
lime	2590	lime gy	3572
shale and lime	2665	lime gy some porosity	3577
shale and lime shells	2740	lime gy hd	3606
shale and lime	2835	lime dk gy	3615
sdv shale lime shells	2855	lime gy & shale	3634
broken lime	2875	lime gy lgt	3640
shale and broken lime	2890	Total Depth.	
shale	2900		
broken lime	2950	Ran 312' 5 $\frac{1}{2}$ " csg for liner.	
broken lime and shale	2975	Cemented at 3640	
lime	3000	Drld cement to 3591	
lime and shale breaks	3065	Perf. csg w/35 holes 3581-36 no sho	
shale	3095	Perf. csg w/33 " 3572-77 no shows	
lime	3120	Acidized w/500 Gals. Acid	
shale and lime shells	3185	Swbd 1 $\frac{1}{2}$ BWPH. Cem. off perforation	
shale	3200	Perf. csg w/36 holes 3513-26	
shale and lime shells	3230	10 gals wtr per hr	
shale	3235	Cemented off perforations	
lime	3240	Perf. csg w/126 holes 3425-46	
shale	3243	Swbd scum of oil & 20 gals.	
lime	3245	wtr per hr for 6 hrs	
shale	3293	Treated w/1000 Gals. Acid	
lime	3304	Swbd 5 BWPH; POB scum of oil	
shale	3331	20 BW in 24 hrs; POB some 20	
lime	3335	days 16 hrs per day & averaged	
shale	3340	$\frac{1}{2}$ BO & 30 BWPH	
shale	3345	Plgd & abnd 10-25-45	
lime	3350		
S.L.M. C. 3550 equals 3557			
lime shells	3371		
lime	3375		
S.L.M. 3375 equals 3374			
chat and lime little shale	3380		