

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA, KANSAS

Location. CNL SW $\frac{1}{4}$

Sec. 30 T. 27 R. 10W

Casing Record.

County Kingman **NOV 25 1933**

10" Farm. Interurban Realty
 20" 8 $\frac{1}{2}$ " Company. Skelly Oil Co.
 15 $\frac{1}{2}$ " 65/8" 3410 Contr.
 12 $\frac{1}{2}$ " 247'9 53/16" Comm 9-8-33

No. 1
 Comp. 10-11-33

Total Depth. 3452 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.



Figures Indicate Bottom of Formations.

Elevation.
 Initial Production.
 Flow 431 bbls 7 hours.

Date Issued. 11-25-33

| Formation | Depth | Formation | Depth. |
|-----------------------------|-------|--|--------|
| surface | 10 | shaley lime grey and shale | 3403 |
| sand | 125 | lime grey and shale | 3407 |
| sand and shale | 185 | lime | 3417 |
| sand hard | 250 | S.L.M. 3417 equals 3414 | |
| shy shale and shells | 790 | cored from 3390 to 3417 | |
| shale and shells | 1000 | cherty lime grey brown | 3421 |
| shale shells and salt | 1150 | lime | 3425 |
| shale and shells | 1305 | lime cherty brown | 3429 |
| shale and lime shells | 1690 | lime dark brown grey with little | |
| lime and small shale breaks | 1750 | shale soft | 3442 |
| shale and lime shells | 1805 | 2100' oil in hole | |
| shale and lime | 1860 | Gas est 50,000,000 | |
| shale and shelly lime | 1995 | S.L.M. 3434 equals 3438 | |
| lime and shale | 2055 | lime dark brown grey | 3447 |
| broken lime and shale | 2120 | lime fine grey | 3452 |
| shale and lime shells | 2190 | TD. | |
| shale and shells | 2280 | | |
| lime and shells | 2325 | | |
| shale and lime shells | 2435 | 3000' oil in hole 3447 no gas increase | |
| shale and shells | 2500 | from 3447-52 | |
| lime and shale | 2570 | Plugged back 3445 to shut off water. | |
| lime | 2705 | lead wool 3445-3444. S.L.M.C 3444 = 3451 | |
| shale and lime | 2785 | Lead wool 3451 - 3450 $\frac{1}{2}$ | |
| shale and lime shells | 2865 | | |
| shale and shells | 2910 | | |
| lime | 2935 | | |
| shale and lime shells | 3000 | | |
| lime | 3050 | | |
| shale and lime shells | 3105 | | |
| shale and lime | 3165 | | |
| S.L.M. 3165 equals 3155 | | | |
| lime | 3250 | | |
| lime | 3290 | | |
| lime small shale breaks | 3325 | | |
| lime | 3390 | | |
| S.L.M. 3340 equals 3343 | | | |
| shale blk | 3395 | | |
| shaley lime blk | 3399 | | |