

15-27-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Freeland No. 2

SEC. 13 T. 27 R. 10W
NW NW SE

Total Depth. 4272
Comm. 8-7-51 Comp. 8-23-51
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 10-6-51

County Kingman
KANSAS



CASING:
8 5/8" 316' cem w/250 sx's.

Elevation. 1730 BB
1727 (m)

Production. dry

Figures Indicate Bottom of Formations.

sand	125	
red shale, shells	250	
red bed	316	
sand, shale, red bed	705	
anhydrite	720	
shale, shells	1300	
broken lime	1530	
lime, shale	1635	
lime	1645	
lime, shale	2315	
shale, shells	2620	
lime, shale	3490	
lime	3875	
lime, shale	3995	
cherty lime	4049	
shale	4060	
shale, lime	4105	
shale	4268	
lime	4272	RTD
Total depth		

Tops:

Brown lime	3464
Lansing	3474
Mississippi	4006
Kinderhook	4083
Viola	4268

DST 4006-17 open 1 hr., good
blow, rec 30' drilling fluid.
Show gas BHP 0
DST 4264-72 open 1 hr. good blow.
rec. 60' oil & gas cut mud &
180' salt wtr. BHP 1180#