

Company SKELLY OIL CO.
Farm North Miles No. 1.

SEC. 19 T. 27 R. 10 W
SEc SE

DEEPENING RECORD

Total Depth. 3517' PB 3490'
Comm. 3-29-32 Comp. 6-8-32
Shot or treated.
Contractor.
Issued. 12-7-46

County. Kingman
KANSAS



CASING:
12 1/2" 270'
53/16" 3371 1/2'

Elevation. _____

Production. 4,400,000 G.
Flowed 7 1/2 BOPH

Figures indicate Bottom of Formations.

send	30	gas inc. to 100,000 @ 3400
gravel	40	lime 3408
sand	90	1000' oil 3406-08
red bed	250	650,000 gas 3408
sand	265	lime 3416 1/2
red rock	272	10 BO hours flowing
red bed	322	lime 3447
red bed & gyp	385	1,100,000 gas 3416 1/2 gauged
shale	500	1,200,000 gas 3421 gauged
shale brkn brwn	600	2,300,000 gas 3434
shale blue	770	3,400,000 gas 3436
brkn shale & lime		lime 3453
shales	1070	flowing 7 1/2 BOPH
shale brkn	1400	lime 3457
gyp crystal	1490	lime & little shale 3461 1/2
lime & shale	1556	lime 3487
lime	1605	lime w/ little sand &
red rock	1620	shale 3469
lime	1676	no increase
lime sdy	1735	lime 3490
sand	1755	4,400,000 gas 3477
lime	1779	3490=3489 SLM
lime & shale	1867	lime 3493
shale red	1887	shale 3494
lime & shale	1902	lime 3496
lime	1925	Total Depth-SLM.
red rock	1935	
shale	1985	DEEPENING RECORD
lime sdy	2002	Comm. 3-3-45 Comp. 5-2-45
lime	2007	Production - 1BO, 40 BW
lime sdy	2017	Attempted to drill to lower
lime (sh gas 2025)	2062	Lansing Pay zones; drld lime
lime & shale	2290	to 3517
shale brwn	2325	where hole was lost because
lime brkn	2380	of mechanical troubles
shale	2434	Total Depth.
lime brkn	2500	
lime w/shale brks	2536	Plugged back to 3490
lime & shale	2624	1000 acid
lime	2660	Re-completed from upper
shale	2680	Lansing zones
lime	2722	
lime brkn	2760	
shale sdy brwn	2850	
lime	2880	
shale sdy	2905	
lime	2995	
shale	3050	
lime brkn	3170	
lime & shale	3265	
lime w/shale brks	3320	
shale & lime shells	3376 1/2	
lime & shale	3377 1/2	
lime w/little		
chert	3386	
lime oolitic	3393	
lime & shale	3397 1/2	
25,000 gas @ 3390		
rainbow oil	3393	