


SKELLY OIL CO.
Alice J. Conley No. 2.

SEC. 20 T. 27 R. 10W
NE SE NW SW
691' fr NL 1208' fr WL N $\frac{1}{2}$ SW

County. Kingman

Total Depth. 3950'
Comm. 1-18-38 Comp. 3-4-38
Shot or Treated.
Contractor. Thurmond & Lipscomb
Issued. 4-2-38 Rotary 3934
Cable 3950



CASING:
13" 363'
7" 3927'

Elevation.

Production. 63,688,805 G.

Figures Indicate Bottom of Formations.

sand	110	Btm 2' very drk cherty lime.
red rock & sand	335	Porous w/ little saturation &
red rock	370	show sulphur gas.
red rock, sand shells	570	lime 3865
shale & shells	932	Top Kinderhook dolomite 3862
salt	1285	dolomite brown 3883
shale & lime	1385	shale 3929
lime	1455	Top Viola lime 3926 SIM
lime & shale	1495	hrd greyish blue chert &
lime	1575	cryst dolomite 3933
shale & lime	1665	cored 3933-3937 Rec 2'
lime	1745	all drk grey cryst dolomite.
shale & lime	1830	porous w/ sh gas
lime	1985	Standardized
lime & shale	2260	Steel line corr 3937-3934
shale & lime shells	2340	Viola lime top, and 7" casing
lime	2380	points above corrected to this
lime & shale	2525	depth.
lime	2565	brown cryst dolomite w/
shale & lime	2595	little grey chert 3937
lime	2735	porous w/ sh gas
shale & lime	2780	brown cryst dolomite w/
lime	2880	little grey chert 3940
shale & shells	2920	porous w/ sh gas
shale & lime	2980	brown cryst dolomite 3950
lime	3210	sh gas, formation hrd 3948-3950
lime & shale	3375	Total Depth.
lime	3395	
shale & lime	3415	Top Lansing lime 3424, oil 3424 3506
lime	3420	Top Kinderhook dolomite 3862
cored 3420-3434 Rec 7'		Top Viola lime 3926, gas 3926-3950
Top 1' grey banded limoy shale		Main body pay formation.
3 $\frac{1}{2}$ ' grey banded shaley lime.		
No porosity or sat.		
Btm 2 $\frac{1}{2}$ ' dense grey & brown lime		
Slight por & sat.		
Top Lansing lime 3424		
cored 3434-3444 Rec 4'		
Top 3' drk grey lime		
Btm 1' dense brown & grey lime.		
Slight por & sat.		
dense grey cherty lime 3449		
cored 3449-3464 Rec 8'		
Top 4' brown & grey lime.		
Slight sat. fair por &		
good sh oil.		
Btm 4' dense grey cherty lime w/		
strks dolomitic shale.		
hrd dense cherty lime 3465		
lime cherty very hrd 3485		
lime grey dense 3490		
porous & oil stained		
cored 3490-3506 Rec 8'		
Top 3' dense grey cherty lime.		
No shows		
2' grey por. limo. sh gas.		
1' grey por. oolitic & cryst.		
lime. sh gas		
Btm 2' very drk cherty lime. Por.w/		
little sat. & sh sulphur gas.		