

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - ANDERSON-PRICHARD OIL CORP.
Farm - Bayer No. 1

SEC. 24 T. 27 R. 10W
NE NW NW

Total Depth. 4322

Comm. 7-20-51

Comp. 8-5-51


County. Kingman

KANSAS

Shot or Treated.

Contractor. Birmingham-Bartlett Drlg. Co.

Issued. 9-22-51



CASING:
8 5/8" 288' cem. w/250 sx
5 1/2" 4141' cem. w/150 sx

Elevation. 1756 RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	110
shale & shells	205
red bed	288
sand, red bed & shale	535
anhydrite	550
shale & shells	1350
shale & lime	1520
lime	1645
shale & lime	2350
shale	2525
lime	2545
lime & shale	3500
lime	3960
shale & lime	4015
lime	4030
miss. lime	4050
cherty lime	4090
cherty lime & shale	4110
shale	4306
shale & lime	4322
Total Depth	

Tops:

Lansing	3511
Miss.	4030
Viola	4316

DST: 3849-60, open 30 min.
weak blow. rec. 35' very
slightly gas & oil cut mud.
DST: 4030-50, open 1 hr.
Strong blow. rec. 150' gas
and oil cut mud. S.I.P. 750#.
DST: 4315-22, open 1 hr. good
blow. rec. 120' gas cut mud
& 600' salt wtr. BHP 1350#.