

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

SKELLY OIL COMPANY.
Wendel Leisman No. 6

SEC. 29 T. 27 R. 10W.
SE NW NW NW
596 fr NL 596 fr WL

Total Depth. 2150
Comm. 10-25-35 Comp. 11-13-35,
Shot or Treated.
Contractor. Southern and Thurmond.
Issued. 1-18-36.

County. Pratt.



CASING.

Rotary.

10" 270' 65/8" 1993'

Elevation.

Figures Indicate Bottom of Formations.

Production. Gauge
6,510,000 gas. with
some salt wtr.

sand	60
red bed and sand shells	255
red bed and sand shells	285
shale and lime shells	1130
salt	1265
shale and lime shells	1370
shale and lime shells	1455
lime and shells	1514
shale and lime shells	1780
broken lime	1825
lime and shells	1881
shale and lime shells	1985

cored 1985-2002 Rec. 9'.

First 6" shelly grey porous lime.
next 3½' grey shale with little lime.
next 4' hard dark sdy shale
bottom 1' dense grey lime with little
gas (hard)

Top gas pay 1993 Reamed core hole to
2002' and drilled deeper as follows-

shale and lime shells	2135
lime	2150

Total Depth.

sdv dolomite 1993-2150'