

SKELLY OIL COMPANY.
Interurban Realty Co. No. 3


SEC. 30 T. 27 R. 10W.
SE SE NW SW
1250' fr NL 1250' fr WL
SW $\frac{1}{4}$

Total Dpth. 4154 P.B. 4023.
Somm. 2-1-37 Comp. 4-12-37
Shot or Treated.
Contractor. Southern and Thurmond.
Issued. 6-5-37

County Kingman.

CASING. Rotary 4023
Cable 4154

13" 334'
85/8" 4016'
7" 4088



Elevation.

Production. 48,400,000G.

Figures Indicate Bottom of Formations.

surface soil sand & clay	65	Cored 4000-4012	Rec. 6' all dark grayish green Kinderhook shale with 2-3" streaks of brown dolomite.
sand and red rock	325		
red rock	340		
red rock & shale	780	cored 4012-4016	Rec 4' All dark green pyritic Kinderhook shale.
shale and shells	1055		
salt and shale	1305		dark green pyritic shale 4016- 4020
shale and lime	1810		dense blue chert and dolomite 4022
lime	1900	cored 4022-4027	Rec 3' Top 6" bluish grey chert and dolomite
shale and lime	1965		2' grey and brown dolomite show gas.
lime	2020		Btm. 6" same. with show gas and slight oil sat..
lime and shale	2350		Steel line corr. 4027- 4023
shale	2475		Top Viola lime 4017
shale and lime	2515		dark brown and grey dolomite 4023-4027
shale	2565		porous and oil stained. carried show gas but no oil.
lime	2635		mod soft brown dolomite 4032
lime and shale	2980		oil stained and porous. show gas but no oil.
lime	3010		brown cherty Dolomite with little grey chert 4036
shale and lime	3035		slight porosity and show gas.
lime	3070		limo 4086
lime and shale	3145		S.L.Corr. 4086 equals 4088
lime	3290		brown cherty dolomite 4090
			dense brown cherty dolomite with little sand 4096
shale	3405		dark grey sand with 10% green Simpson shale 4100
shale and lime	3420		Baso Viola lime and Top Simpson shale at 4098
Top of Lansing 3412			dark grey sand with 15% green simpson shale 4104
Cored 3420-3436. Rec 16' Top 2' Grey shale			light grey sand with 75% green shale 4109
10" limo slight porosity and oil stained.			Top Wilcox sand 4109
9' lime			oil stained. No Sat. show gas.
quite porous and oil sat.			dark brown granular sand 4117
4 1/2' lime. oil Sat.			gas gauged 16,600 M.
btm. 1 1/2' lime			S.L.Corr. 4117 equals 4121.
lime 3436- 3470			shale green with 50% sand Oil 4125
lime and shale 3500			grey stained.
lime 3559			brown and grey sand mod hard 4127
good sat. 3490-3510			oil stained.
S.L.Corr. 3559- 3555			after drilling to 4127 bailed hole down to 1300' gas gauged 9,860 M. cu ft. with no show oil.
lime 3570			no samples caught 4127- 4152
cored 3570-3586. Rec 11' Top 8' lime			dark shale with 20% sand soft 4154
Btm. 3' dark grey shale.			Total Depth.
Base Lansing 3583.			P.B. 4023. Gas gauged 8,960 M.G.
shale 3586- 3588			Gas gauged 52,900 M. G. 8 Hr.
cored 3588-3604 Rec 4' Top 6" dark grey shale.			
3' 1' lime streaked with grey shale.			
1' hard grey lime dark chert.			
3" grey lime slightly Sat.			
2' dark chert.			
6" lime.			
1" Grey lime. oil Sat.			
Btm. 6" grey lime.			
shale and lime 3604- 3625			
lime 3860			
shale 3985			
cored 3985-3991 Rec 6' all dark grey kinderhook shale.			
shale 3991- 4000			