

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY,
Union National Bank Bldg, Wichita, Kansas.


SKELLY OIL COMPANY.
J.M. Ratcliff No. 6

SEC. 30 T. 27 R. 10W.
SW NW NW
930' fr NL 440' fr WL
County. Kingman.

Total Depth. 3473
Comm. 9-17-35 Comp. 10-11-35
Shot or Treated. 1500 gal, 3000 gal, 5000 gal.
Contractor. Southern and Thurmond.
Issued. 12-28-35.

Casing. Rotary 0 to 3435
Cable 3435- 3473'

12 $\frac{1}{2}$ " 333' 7" 3432



Elevation.

Production. 66 bbls.
Est 80,000 gas.

Figures Indicate Bottom of Formations.

surface soil	60
red bed and sand shells	290
shale and sand shells	345
shale and shells	730
shale and lime shells	1025
salt and gyp shells	1155
shale and lime shells	1410
shale and lime shells	1730
lime	1775
shale and lime shells	2000
lime	2045
shale and lime shells	2205
lime shale and shells	2265
shale and lime shells	2360
shale and shells	2425
shale and lime shells	2565
lime	2665
shale and shells	2730
lime	2760
shale and lime shells	2860
lime	2880
shale and shells	3150
lime	3320
shale and lime shells	3335
lime	3360
lime and shale	3380
shale and broken lime	3426
cored 3426 -3435 Rec 9'	
Top 7' Bended grey lime and shale	
Bottom 2' Dense grey and fossiliferous	
lime slight sat. and porosity.	
dark dolomite lime with little	
brown lime	3439
smell gas. and bailer showed	
little free oil	
dark grey lime with little	
brown lime	3445
showed 50' oil in hole.	
lime dark grey hard	3450
no oil or gas Inc.	
lime hard dark grey	3454
no oil or gas increase.	
lime hard dark grey with 40%	
dolomitic lime	3459
no oil or gas increase.	

lime hard grey 3463
Steel line corr. 3463 equals 3460
lime hard grey 400' oil hole 3463
lime soft med dark 3468 $\frac{1}{2}$
lime hard dark grey 3473
Total Depth.
Little increase of oil and gas 500'
oil in hole 3468 $\frac{1}{2}$

Lansing lime 3433 3475
main body pay formation.