

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


SKELLY OIL CO.
H.N. Michener No. 1

58082
SEC. 31 T. 27 R. 10 W.
C SW SW
660' f SL 660' WL SW $\frac{1}{4}$

Total Depth. 4260
Comm. 3-3-42 Comp. 3-20-42
Shot or Treated.
Contractor. Bodine Drilling Co.
Issued. 4-18-42

County Kingman.

Rotary.



CASING.

85/8" 360' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface soil and sand	100	
red bed	365	
red bed	485	
shale and shells	1050	
salt	1150	
shale and salt	1275	
shale and shells	1455	
shale and lime	1585	
lime	1665	
shale and lime	1800	
sdv lime	1900	
lime	1990	
lime and shale	2735	
shale	2780	
lime	2805	
lime and shale	2880	
lime	2930	
lime and shale	3100	
lime	3220	
lime and shale	3300	
lime	3340	
shale	3405	
shale and lime	3465	
lime	3475	
shale and lime	3540	
lime brown	3545	
shale dark grey	3565	
med soft grey and brown lime	3574	Medium porosity, no oil
hard grey crystalline lime	3580	No porosity or sat.
soft grey fossiliferous oolitic lime	3588	porous no oil
hard grey lime	3695	
lime	3920	
shale	3955	
shale and lime	4002	
cherty lime	4050	
shale	4245	
grey chert and grey cherty crystalline dolomite	4248	Good porosity, no oil stain or Sat.
soft grey coarsely crystalline dolomite, and chert	4254	Porous, probable water.
crystalline dolomite	4256	slight porosity, no oil saturated.
med soft, grey coarsely cryst. dolomite	4260	Good porosity, probable water.
Total Depth.		

TOPS.

Lansing lime 3565
Kinderhook Dolo. 4178
Viola lime 4245