

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company SKELLY OIL CO.  
Farm North Miles No. 2.

SEC. 19 T. 27 R. 10 W  
C WL SE

DEEPENING RECORD

Total Depth. 3665'  
Comm. 9-28-33 Comp. 11-1-33  
Shot or Treated.  
Contractor.  
Issued. 12-7-46

County. Kingman  
KANSAS



CASING:  
12 1/2" 352'  
65/8" 3473'

Elevation. \_\_\_\_\_

Production. 372 B0,  
392,000 G.

Figures Indicate Bottom of Formations.

shale sdy	130	lime brwn med washed	
red rock	150	free oil	3502
red rock & sand	170	lime med brwn w/	
red rock	240	little chat	3504 1/2
red rock sand&shells	352	lime brwn w/little	
sdv shale & shells	470	shale	3509
shale & shells	1040	lime brwn	3515
salt	1145	SLM 3515 equals 3517 1/2	
shale & shells	1550	Total Depth.	
shale & lime shells	1625		
lime	1735	<u>DEEPENING RECORD:</u>	
shale & lime shells	1780	(to test lower Lansing	
lime	1800	zones)	
shale	1820	Comm. 1-3-45	
shale & shells	2175	Comp. 3-27-45	
lime	2195	Pmpd 288 B0 plus 12% wtr	
shale & shells	2535	in 24 hrs	
shale	2550		
lime hd	2570	limestone	3665
shale & shells	2590	Total Depth.	
lime hd	2680		
shale & lime shells	2745	sh oil 3542-55	
lime brkn & shale	2775	sh oil 3616-20	
lime & shale	2805		
shale & shells	2930	Cem. 208'5" liner @3634	
lime	2955	Perf. w/84 holes 3542-55	
shale	2980	Perf. w/41 holes 3615-20	
shale & shells	3045	Treated 750 Gals. Acid	
shale	3065	3542-55	
lime	3160	Well started flowing	
shale & shells	3170	Pmpd 288 B0 plus 12% wtr	
shale & lime shells	3223	in 24 hrs.	
lime	3230		
shale & lime	3290		
shale	3295		
lime	3315		
3320 equals 3324 CSLM			
shale	3304		
lime	3340		
lime shells & shale	3415		
lime	3435		
shale	3477		
lime SLM 3493			
cored 3477-93 rec. 10'			
top 5' porous foss.			
lime showing oil			
stains & heavy oil			
residue, Lower 3'.			
lower 5' gy to brwn			
dense & xlyn gy &			
brwn lime some oil			
saturation			
Standardizing			
lime med gy, little			
shale brwn	3497		