


SKELLY OIL COMPANY
Wendel Leisman No. 6

SEC. 29 T. 27 R. 10W
SE NW NW ~~10~~ 11
596 fr NL 596 fr WL

DEEPENING RECORD

Total Depth. 3433'
Comm. 10-25-35 Comp. 11-13-35
Shot or Treated.
Contractor. Southern and Thurmond
Issued. 5-13-44

County. Pratt



Rotary
CASING.

Elevation.

10" 270' 65/8" 1993'

Production. Gauge
6,510,000 gas, with
some salt wtr

Figures Indicate Bottom of Formations.

sand	60
red bed and sand shells	255
red bed and sand shells	285
shale and lime shells	1130
salt	1265
shale and lime shells	1370
shale and lime shells	1455
lime and shells	1514
shale and lime shells	1780
broken lime	1825
lime and shells	1881
shale and lime shells	1985

DEEPENING RECORD:

Comm. 10-28-43 Comp. 11-30-43
Prod. - 30 30 12 hrs

lime	4190
lime	4140
lime & shale	3325
shale	3510
lime	3590
shale & lime	3655
shale	3770
lime	3800
shale	2965
lime	3290
shale	3346
lime crystalline	3360
lime	3433

cored 1985-2002 Rec. 9'
First 6" shelly grey porous lime
next 3 1/2' grey shale with little lime
next 4' hard dark sdy shale
bottom 1' dense gy limo w/little
gas (hard)

Total Depth.

Top gas pay 1993 Roamed core hole to
2002' and drilled deeper as follows-

shale and lime shells	2135
lime	2150

Total Depth.

Top Lansing 3346
Oil pay 3401-05 &
3412-18

sdv dolomite 1993-2150'