

June 22, 1979

C Union Drilling Company, Inc.
505 Union Center
Wichita, Kansas 67202

Re: Rupe Oil Company, Inc.
#1 FREELAND
C S/2 NE of Section 13-27S-10W
Kingman County, Kansas

O Gentlemen:

The following contains drilling instructions for the above captioned 'test':

P

Mud:	Davis--have mud in shape for DST by 1500'.
Surface Casing	250'
Cement:	Halliburton
Drill Time	1' from 1500' to RTD.
Samples:	10' from 1500' to 1610', 30' from 1610' to 2100', 10' from 2100' to 2320' and 5' from 2320' to RTD.
Gas Detector:	Please mark connections on Gas Detector Chart from 1500' down and call Geologist if horn blows (Mud viscosity 38, water loss 10 or less)
Call Depth:	1500' - STOP at 1610'
Geologist:	'Chuck' Kuhl - Office Home 

Y
RUPE OIL COMPANY, INC.

WGC:fwl

William G. Clement,
Petroleum Geologist