

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- MESSMAN-RINEHART OIL CO.
 Farm- Park No. 2

SEC. 14 T. 27 R. 11W
 NW SW SW

Total Depth. 4115'

Comm. 4-9-59

Comp. 4-22-59

Shot or Treated.

Contractor. Messman-Rinehart Oil

Issued. 8-8-59

County Pratt

KANSAS



Elevation. 1810' KB

Production. Dry

CASING:

10 3/4" 300' cem w/200 sx.

4 1/2" 4104' cem w/150 sx.

Figures indicate Bottom of Formations.

clay & soil	50
sand	150
shale & red bed	200
red bed	300
shale & red bed	1140
shale & shells	1340
Anhydrite streaks	1380
shale	1510
lime & shale	1650
lime	1970
lime & shale	2730
shale	2770
lime	2910
lime & shale	2980
lime	3344
lime & shale	3460
shale	3590
lime & shale	3640
lime	3717
lime & shale	3747
lime	3815
lime & shale	3840
lime	3980
lime & shale	4060
lime	4085
cherty lime	4115 RTD
Total Depth	

TOPS: SAMPLE

Heebner	3430
Brown Lime	3609
Lansing	3627
Mississippi Chat	4099

Perf. 3942-46' w/4 shots per ft., show oil
 and gas on gun.

4-28-59 Treated w/1000 gal. acid, made 1/2 BOPH
 (show gas & no wtr.) Perf. 3812-16' w/4 shots
 per ft. Jet.

4-29-59 Treated w/500 gal. acid.